

## UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS:

\* never Drilled

Trans file

DATE FILED 7-26-57

LAND: FEE &amp; PATENTED STATE LEASE NO. ML-3156 PUBLIC LEASE NO.

INDIAN

DRILLING APPROVED: 7-26-57

SPUDDED IN:

COMPLETED:

INITIAL PRODUCTION:

GRAVITY A. P. I.

GOR:

PRODUCING ZONES:

TOTAL DEPTH:

WELL ELEVATION: 4523' GL

DATE ABANDONED: LOCATION ABANDONED 7-26-58

FIELD OR DISTRICT: Th Aneth 7/86

COUNTY: San Juan

WELL NO. STATE THREE 33-16

43-037-11072

LOCATION: 1980 FT. FROM ~~N~~ (S) LINE, 1982 FT. FROM (E) ~~N~~ LINE. NW SE QUARTER - QUARTER SEC. 16

10

TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
40 S	24 E	16	SHELL OIL COMPANY				

Scout Report sent out

Noted in the NID File

Location map pinned

Approval or Disapproval Letter

Date Completed, P. & A. or  
operations suspended

Pin changed on location map

Affidavit and Record of A & P

Water Shut-Off Test

Gas-Oil Ratio Test

Well Log Filed


- ☒
- ☒
- ☒
- ☒
- ☐
- ☐
- ☐
- ☐
- ☐
- ☐

*Location abandoned  
Well never drilled*

522-91  
for

(SUBMIT IN DUPLICATE)

LAND:



**STATE OF UTAH**  
**OIL & GAS CONSERVATION COMMISSION**

STATE CAPITOL BUILDING  
 SALT LAKE CITY 14, UTAH

Fee and Patented.....☐  
 State .....☒  
 Lease No. ML 3156  
 Public Domain .....☐  
 Lease No. ....  
 Indian .....☐  
 Lease No. ....

## SUNDRY NOTICES AND REPORTS ON WELLS

Notice of Intention to Drill..... Notice of Intention to Change Plans..... Notice of Intention to Redrill or Repair..... Notice of Intention to Pull or Alter Casing..... Notice of Intention to Abandon Well..... ..... .....	<input checked="" type="checkbox"/>       	Subsequent Report of Water Shut-off..... Subsequent Report of Altering Casing..... Subsequent Report of Redrilling or Repair..... Supplementary Well History..... ..... .....
--	---	--

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

July 24, 1957

State Three

Well No. 33-16 is located 1980 ft. from SW line and 1982 ft. from EA line of Sec. 16

SE 16                      40S                      24E                      SLBM

(¼ Sec. and Sec. No.)                      (Twp.)                      (Range)                      (Meridian)

Aneth                      San Juan                      Utah

(Field)                      (County or Subdivision)                      (State or Territory)

The elevation of the derrick floor above sea level is 4523 feet. (Approx. ground)

A drilling and plugging bond has been filed with State of Utah

### DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important work, surface formation, and date anticipate spudding-in.)

1. Drill 11" hole to 1200'±.
2. Cement 8-5/8" casing at 1200'± with 400 sacks pozmix and 200 sacks construction cement.
3. Drill 7-7/8" hole to 5408'±.
4. Cement 5-1/2" casing at 5408'± with 200 sacks construction cement.
5. Drill 4-3/4" hole to 5453'±.
6. Acidize with 200 gal mud acid and 2000 gal XFW acid.
7. Swab well in and make production test.
8. Drill 4-3/4" hole to 5588'±.
9. Wash formation with 420 gal mud acid.
10. Swab well into production, establish initial rate.

I understand that this plan of work must receive approval in writing by the Commission before operations may be commenced.


Company Shell Oil Company

Address 101 South Behrend By B. W. Shepard

Farmington, New Mexico Title Exploitation Engineer

INSTRUCTIONS: A plat or map must be attached to this form showing the location of all leases, property lines, drilling and producing wells, within an area of sufficient size so that the Commission may determine whether the location of the well conforms to applicable rules, regulations and orders.

R.24E. S.L.M.



ELEVATION DATA

GROUND 4523' UG  
MATT  
D.F.  
K.B.  
B.M. 4536.3'


REFERENCE POINT DATUM-

1"x2" STAKES SET AT 10' N., S., E., & W. OF LOC.  
1"x2" stake and 3' flag set at 140'E., 110'S., 140'W. & 130'N. of Loc.  
1"x2" hub and 10' flag set at Loc. being 1982'W. & 1980' N. of  
the SE Cor. of Sec. 16, T.40S., R.24E., S.L.M.  
1"x2" hub and 3' flag bears N. 130' from the Loc. for B.M.

This is to certify that the above plat was prepared from field notes of actual surveys made under my supervision, and that the same are true and correct to the best of my knowledge and belief.

July 19, 1957

*John A. Kroeger*  
John A. Kroeger, Reg. L.S.  
Utah Reg. No. 1648



Drawn By: Ritter

Checked By: A.C.T.

Date: 7/19/57

SHELL OIL COMPANY

Scale 1" = 1000'

LOCATION OF STATE III - 33 - 16

SAN JUAN COUNTY, UTAH, SEC. 16, T.40S., R. 24 E., S.L.M.

July 26, 1957

Shell Oil Company  
101 South Behrend  
Farmington, New Mexico

Gentlemen:

This is to acknowledge receipt of your notice of intention to drill Well No. State Three 33-16, which is to be located 1980 feet from the south line and 1982 feet from the east line of Section 16, Township 40 South, Range 24 East, SEEM, San Juan County, Utah.

Please be advised that approval to drill said well is hereby granted.

Yours very truly,

OIL & GAS CONSERVATION COMMISSION

CLEON B. FEIGHT  
SECRETARY

CBF:cn

cc: State Land Board  
Rm. 105, State Capitol  
Salt Lake City, Utah

DR-USGS